HIGHWAY DEPARTMENT
920 THIRD STREET
PO BOX 108
Hammond, WI 54015-0108
Phone: (715) 245-4200
Fax: (715)-245-4199

Website: sccwi.gov

February 6, 2019

Road Improvement Projects Scheduling

In anticipation of another year in road improvements on the County Trunk Highway System, the Highway Department has begun the process of preparing a tentative schedule for maintenance on our roadways.

To help us in our scheduling, we are asking the Towns, Villages, and Cities that may be requesting our services to provide us with a rough estimate, including project length, of what type of projects you may be considering.

We are seeing an increase in the cost of hot mix this season.

Providing us with your tentative 2019 projects within the next couple of weeks would help us in our planning. I realize that some of you have already begun this process with us. However, I ask that you still fill out the attached form.

Please contact me, or any member of our staff, for any assistance we can provide. Thank you for completing this form to help us better serve your needs in 2019.

Sincerely,

Mike Van Keuren
Assistant Patrol Superintendent
Cell (715) 760-1902

Cc: Robbie Krejci, St. Croix County Highway Commissioner
Joel Allen, Patrol Superintendent

Please fill out your anticipated needs for 2019 and return to us via
E-mail michael.vankeuren@sccwi.gov or please see page 1 for the fax number.
You may also mail to the address on page one.

The prices listed below are general budget figures for you to use as a guide.
We will have better knowledge for our estimates the first part of April.

Please note that filling out this form in no way obligates you for this year. It is a rough estimate that will be used for us to make sure we have the materials needed on hand. These materials are strategically placed in certain areas to lessen hauling costs to you.

Town/City/Village = **Village of North Hudson**

Blacktop: 22' wide x 2.5" thick - $125,600 per mile _____ miles
(Includes milling, prep., signing, & 2' wide gravel shoulders)

Seal Coat: 22' - $16,000 per mile _____ miles
(Crack filling and/or spray patching is recommended prior to seal coat)

Add Gravel Base: 2" - $17,000 per mile _____ miles
3" - $25,000 per mile _____ miles

Crack Fill: $4,000 per day _____

AMZ "spray patch" - $4,500 per day _____
(Usually 1.5 miles per day)

Culvert Replacement: - 18" - $4,000 24" - $5,000 _____
(Recommend prior to paving or as inspection indicates)
(Class 3 plastic pipe is also an option)
Culvert Patch: - $1,400 _____

Pot hole hand patch: - Time and Materials

Deer pick up for 2020 **Expected to be < $75.00** **yes or no** _____

Mowing one (1) pass top cut $2000 _____

Mowing one (1) pass three gang-through roads only $4500 _____

Guard rail spraying **yes or no** _____

Right of Way Spray Application **yes or no** _____

(For invasive weeds and PGR (Plant Growth Retardant)) approx.. $114/lane mile

******Please call if you have any questions regarding ROW Spray Application******

Widening/Wedging/Reconstruction may be required to accept desired pavement & shoulder width (cost dependent upon scope).